



PROPERTIES

We build trust..

Date: 21.10.2024

SRI SAIS INFRO PROJECTS  
H.No: 2-51/54/70C,  
Srujana Dream city colony  
Isnapur,  
Patancheru mandal,  
SANGAREDDY  
TELANGANA-502319  
Mobile:9966620909  
9177458077

| S.No                                                                                                                                                                                                                                                                                                                                                        | DESCRIPTION OF WORK                                                                                                                                                                                                                                                                                   | UOM | QUANTITY     | NET RATE | AMOUNT              |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------------|----------|---------------------|
| 1                                                                                                                                                                                                                                                                                                                                                           | Supply and laying of WMM (Wet Mix Macadam) 6" loose thick, after compaction 4" inch thick (40 mm 40 %, 20 mm, 20 %Dust 30 % all mix 12mm 10 %). This are all mixing, spreading wet mixing after dozer leveling and rolling with Vibro max vibrating roller, watering with laborformation compunction. | Sft | 20910.00     | 25.00    | 5,22,750.00         |
| 2                                                                                                                                                                                                                                                                                                                                                           | KERB STONE :- After completing the roads a will designed pre-cast site make RCC curving stone with. Saucer Kerb stone will be laid on both sides of the roads. Kerbing stone with dimensions of 6"x16"x2' feet length Curbing stone                                                                   | Sft | 2092.00      | 200.00   | 4,18,400.00         |
| 3                                                                                                                                                                                                                                                                                                                                                           | Providing and laying M25 Grade Concrete 6"inch thick and using 20 mm and downgraded machine crushed stone aggregate in RCC Road up to finished ground floor level including vibrating, tamping, curing, VDF (Vacuum Dewatering Flooring) and 10mm groove cutting with filling of bitumen emulsion.    | Sft | 20910.00     | 85.00    | 16,58,850.00        |
| <u>Terms and Conditions</u>                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                       |     | <b>Total</b> |          | <b>26,00,000.00</b> |
| <u>Payment Terms:</u><br><br>Mobilization advance as 30% amount out of total work order value<br>Next Payment as per work progress<br>Water and electricity is under our scope<br>Any extra work/(s) should be informed to us, after our approval, works are to be carried out.<br>Layout and Electricity Permissions are under our Scope.<br>Extra 18% GST |                                                                                                                                                                                                                                                                                                       |     |              |          |                     |

Thank you



For Bhavani Properties

Authorized Signatory

Bhavani Guest INN Ground Floor,